

Budget for Yabatalou the Garden Project**Based on the experience of Bagourou****Water well 18 m and fence 250 m**Surface vegetable garden 55 x 70 = 3850 m²

| 1000 Francs CFA = 1,54 euros | X 1000 CFA | EURO |
|--|-------------------|-------------------|
| Two professional well technicians | 450 | 693 |
| Wheelbarrows, shovels and barrils | 100 | 154 |
| Gravel | 155 | 239 |
| Cement for well, basins and fence : 84 sacs | 518 | 798 |
| Concrete iron 8 mm, 56 x 6 m | 112 | 173 |
| Concrete iron 6 mm, 61 x 6 m | 92 | 141 |
| 5 rolls fastening wire | 15 | 23 |
| Corners 50 mm, 31 x 6 m | 372 | 573 |
| Cut and preparation the corners | 37 | 57 |
| Fence 10 x 25 m and transport | 260 | 400 |
| Galvanized wire 700 m | 55 | 85 |
| Door and post | 27 | 38 |
| 15 Tensioners | 15 | 23 |
| Tubes for the distribution basins | 65 | 100 |
| Pose of the fence | 35 | 54 |
| Transport cement and iron with camel chariot x 7 | 70 | 108 |
| Gaz for motorbike transport | 45 | 70 |
| Food for the workers | 52 | 80 |
| Western Union money transfer costs | 38 | 57 |
| Seeds and trees | 87 | 134 |
| Total 2.600.000 Francs CFA | 2600 | 4000 Euros |